Items of work.	Per.	Quantity.
Relieving weir in 3/3 mile—		
69. Earthwork	C. yd.	382
70. Burnt brick in surki mortar	C. ft.	1,496
71. Burnt stone slabs, dressed, 6" thick	S. ft.	830
72. Plastering with surki mortar	Sqr.	18
73. Rough stone work	C. yd.	189
Cart bridges—		
74. Earthwork	C. yd.	85
75. Burnt brick in surki mortar	C. ft.	4,685
76. Plastering do	Sqr.	19·60
77. Burnt stone slabs, 6" thick	S. ft.	675
78. Concrete work	C. ft.	200
Road bridges—		
79. Earthwork	C. yd.	60
80. Burnt brick in surki mortar	C. ft.	3,303
81. Plastering do	Sqr.	12·39
82. Burnt stone slabs, 6" thick, dressed	S. ft.	585
83. Concrete work	C. ft.	213
Right bank channel—		
84. Earthwork excavation	C. yd.	4,838
85. Do embankment	"	3,017
86. Mile stones	No.	4
87. Half-furlong stones	No.	53
88. Bed grade stones	No.	56
89. Index stones	No.	56
90. Constructing aqueduct or syphon to Kodihalla will be designed and quantities given during construction.		
91. Constructing madaboys, 18 in number.		
92. Do relieving weirs, 22 in number.		
93. Do bridges on right channel, 3.		

N. B.—Rate per unit for all the items for which quantities are not given should also be tendered.

R. V. SUNDARAMIER,
Executive Engineer.

HASSAN DIVISION.

NOTICE.

Dated 16th October 1911.

It is hereby notified that the 3rd class travellers' bungalow at Dudda being infected is closed to the public until further notice.

Dated 17th October 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 11th November 1911, for restoring Mugalur Tank, Registered No. 145 of Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Mugalur Tank, Hassan Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of work.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yd.	4,126
Cutting grips	„	1,475
Turfing	S. yd.	2,807
Gravel backing in rear of revetment	C. yd.	733
New stone work	„	1,990
Old stone work	„	434
Preparing and fixing new grade stones with bottom slabs	No.	32
Vis-á-vis stones with bottom slabs	„	32
B. M. stones with bottom slabs	„	2
Register number stone	„	1
Gauge stones	„	2
Breaching the bund, letting out water to facilitate work and refilling the same	C. yd.	768
Proposed new sluice—		
Earthwork, excavating and refilling including consolidation	C. yd.	345
Concrete in surki mortar	C.ft.	355
Brick in surki mortar	„	283
Archwork in do	„	22
Stone slabs, 3″ thick	S. ft.	49
Do 6″ „ dressed	„	70
Preparing holes for upper and lower orifice slabs	Lump sum.	
Fixing gibbets	Lump sum.	
Plastering with surki mortar	Sqr.	2·00
E. I. pipes of 9″ diameter including carting and fixing	R. ft.	54
Baling water	Lump sum.	
Plug and rod	Do	
Left waste weir—		
Earthwork, excavation	C. yd.	221
Blasting rock	„	6
Brick in surki mortar	C. ft.	1,189
Burnt stone slabs, 4 to 6 inches thick, dressed	S. ft.	406
Plastering with surki mortar	Sqr.	2·62
Rough stone work, new	C. yd.	103
Do old, with new jelly	„	22
Clearing draft	„	255

V. AIYASWAMI IYER,
Executive Engineer.

WATER-SUPPLY AND STORES DIVISION.

Abstract Notification dated 19th October 1911.

The attention of the public is invited to the notification dated 12th October 1911, calling for tenders for the supply of fuel to the Pumping Station, Bethamangala, published in page 1207, Part II of the *Mysore Gazette*.

The specification for jungle fuel omitted in last notification is herein published for information.

Specification.

The wood to be jungle fuel.

The maximum and minimum dimensions which will be accepted are given below:—

Length.		*Thickness.*	
Maximum.	Minimum.	Maximum.	Minimum.
24″	18″	7″	3″

The billets are to be sawn and not chopped. Billets of over 7 inches in diameter to be split.

The wood to be stacked by the contractor in the portion approved of by the Executive Engineer or his representative.